

	Remove and Dispose Existing Ceiling Tiles and Insulation from:	Remove and Dispose 168 Existing T-12 Fixtures and Existing Electrical and Switches:	Install & Connect 126 New LED Panels with New Wiring and Dimming Controllers/ Switches: Westgate Model :LP 2X4 -72W-50K-	INSTALL NEW R-30 Insulation to Roof Joists in Rooms	Replace Ceiling Tiles with New Tiles
Library	Approx. 1375 Sq.Ft.	Remove 39 Existing	Install 30 New Fixtures 2 Dimmer Switches	R-30 1375 Sq.Ft.	Approx. 1135 Sq.Ft.
Computer Lab	Approx. 1223.75 Sq.Ft	Remove 33 Existing	Install 24 New Fixtures 2 Dimmer Switches	R-30 1223.75 Sq.Ft	Approx. 1031.75 Sq. Ft.
Room 2	Approx. 866.25 Sq.Ft.	Remove 24 Existing	Install 18 New Fixtures 2 Dimmers Switches	R-30 866.25 Sq.Ft.	Approx 722.25 Sq.Ft.
Room 3	Approx. 866.25 Sq.Ft.	Remove 24 Existing	Install 18 New Fixtures 2 Dimmers Switches	R-30 866.25 Sq.Ft.	Approx 722.25 Sq.Ft.
Room 4	Approx. 866.25 Sq.Ft.	Remove 24 Existing	Install 18 New Fixtures 2 Dimmers Switches	R-30 866.25 Sq.Ft.	Approx 722.25 Sq.Ft.
Room 5	Approx. 866.25 Sq.Ft.	Remove 24 Existing	Install 18 New Fixtures 2 Dimmers Switches	R-30 866.25 Sq.Ft.	Approx 722.25 Sq.Ft.
Total	Approx. 6063.75 Sq. Ft				Approx. 5055.75 Sq. Ft.
	Convert 25 Existing 4'- 4 Bulb T-12 Fluorescent Fixtures to: 2 Bulb LED Dispose Old Ballasts (NON SHUNTED) BULB EIKO LITESPANLED LED15WT8F/48/850KG7DM		Install Dimmer Controller/ Switches		
Resource Room	Convert 9 Existing Fixture	18 Bulbs	2 Dimmers Switches		
School Office	Convert 9 Existing Fixture	18 Bulbs	1 Dimmer Switch		
Principal's Office	Convert 4 Existing Fixture	8 Bulbs	1 Dimmer Switch		
Nurse's Station	Convert 2 Existing Fixture	4 Bulbs	1 Dimmer Switch		
Nurse's Office	Convert 1 Existing Fixture	2 Bulbs	1 Dimmer Switch		
Total	25 Fixtures	50 Bulbs			
	Remove and Dispose 5 Existing 4' Fluorescent Fixtures	Install 5 New Vapor Resistant LED Fixtures Lithonia FEM L48 4000LM LPAFL MD GZ10 40K 80CRI			
Girl's Restroom	Remove and Dispose 3 Existing Fluorescent Fixtures	Install 3 New			
Boy's Restroom	Remove and Dispose 2 Existing Fluorescent Fixtures	Install 2 New			